ANALYTICAL REPORT Prepared by Roy F. Weston, Inc.

National Lead Industries Pedricktown, NJ

1

EPA Work Assignment # 2-476 Project # 3347-21-01-3476 EPA Contract # 68-03-3482

ANALYTICAL REPORT

Prepared by Roy F. Weston, Inc.

National Lead Industries Pedricktown, NJ

May 22, 1991

EPA Work Assignment No. 2-476 Project No. 3347-21-01-3476 EPA Contract No. 68-03-3482

> Submitted to A. Zownir **EPA-ERT**

R. Tobia

Task Leader

S. & A. Section Chief

Project Manager

Analysis by

REAC, Galbraith, & ATEC

Prepared by:

J. Hunter

Reviewed by: Yi-Hua Lin

Table of Contents

Introducti	on		Page	1
Section I				
P	rocedure for Metals in Soils		Page	2
P	rocedures for Miscellaneous Analyses		Page	3
R	esults of Metals in Soil Analysis	Table 1.1	Page	4
R	esults of TCLP Metals Analysis	Table 1.2	Page	5
R	esults of Miscellaneous Analyses	Table 1.3	Page	6
R	esults of the Grain Size Analysis	Figure 1.1	Page	7
Section II				
Q	A/QC for Metals		Page	13
	esults of the EMSL Analysis	Table 2.1	Page	14
	esults of the MS/MSD Analysis in Soils	Table 2.2	Page	15
	esults of the Spike Blank Analysis	Table 2.3	Page	
-	A/QC for TCLP Metals		Page	17
R	esults of the Matrix Spike Analysis	Table 2.4	Page	18
Section II	T .			
	hain of Custody		Page	19
C	ommunications		Page	22
Section IV	,			
D	ata Validation		Page	34
Appendix	A Data for Metals - Soils		Page	A1
Appendix	B Data for Metals - TCLP		Page	В1
Appendix	C Data for HGI, CEC, pH, Bulk Density, and Grai	n Size Analysis	Page	C1
	•	m our i maryon	80	-
Α	ppendices will be furnished on request.			

NLD 001 0161

INTRODUCTION

REAC Laboratory, in response to EPA work assignment 3347-21-01-3476, provided analytical and related services for samples received from the National Lead Industries site on February 19-20, 1991. These services included the following;

- 1) The analysis of six soil samples by the REAC laboratory for aluminum, antimony, arsenic, barium, cadmium, chromium, copper, iron, lead, magnesium, manganese, mercury, nickel, selenium, silver, and zinc.
- 2) The subcontracting of six soil samples for Hardgrove Grindability Index, pH, grain size, cation exchange capacity, and bulk density analyses to ATEC Environmental Consultants.
- 3) The subcontracting of six soil samples to Galbraith Laboratories for TCLP extraction and analysis for arsenic, barium, cadmium, chromium, lead, mercury, selenium and silver.

CASE NARRATIVE

REAC personnel calculated the percent recovery for the lead matrix spike for the TCLP metals analysis to be 57. The laboratory had reported 98 percent, subsequent discussion with the subcontractor revealed that the value had been incorrectly reported and the corrected value is contained in this report.

TCLP extraction and analysis of extracts were initially completed by the subcontracting laboratory employing a single point calibration and the method of standard additions to analyze the extracts. The results for this initial analysis of the TCLP extracts were deemed unsatisfactory and reanalysis was performed using a three point calibration. The results of the reanalysis of the TCLP extracts are presented in Table 1.4. Also, the reanalysis for the mercury occurred after the holding time had expired, however, mercury was not detected in the original analysis or in the reanalysis and the data should not be affected.

00001

ANALYTICAL PROCEDURE FOR METALS IN SOIL

Approximately one gram of sample, weighed to 0.01 g accuracy, was thoroughly mixed with 10 ml 1:1 nitric acid:water, digested and analyzed according to methods contained in Test Methods for Evaluating Solid Wastes, USEPA, SW-846, September, 1987. The results are listed in Table 1.1.

Mercury was analyzed separately on a Varian SpectrAA-300 Atomic Absorption Spectrophotometer equipped with a Varian VGA-76 vapor gas analyzer using method 7471 as given by Test Methods for Evaluating Solid Waste, USEPA, SW-846, September, 1986.

Results of the analyses are listed in Table 1.1.

ANALYTICAL PROCEDURES

Methods for the TCLP and miscellaneous analyses are found in the following references.

Bulk Density was performed using Method D854/E12 American Society for Testing and Materials Results for Bulk Density are presented in Table 1.3.

Cation Exchange Capacity was performed using Method 9080, Test Methods for the Analysis of Solid Waste (SW-846), USEPA 3rd Edition, November 1986. Results for Cation Exchange Capacity are presented in Table 1.3.

Grain Size Analysis was performed using Method 422, American Society for Testing and Materials. The results of the Grain Size Analysis are presented in Figure 1.1.

Hardgrove Grindability Index was performed according to Method D409 American Society for Testing and Materials. Results for the Hardgrove Grindability Index are presented in Table 1.3.

TCLP methodology as described in 40 CFR, Part 261, Appendix II, Method 1311 Test Methods for Evaluating Solid Waste, Physical/Chemical Methods, Vol. 1C, Revision 0, November, 1990. Results for Metals Analysis of TCLP Extracts are presented in Table 1.2.

pH was performed using Method 9010, Test Methods for the Analysis of Solid Waste (SW-846), USEPA 3rd Edition, November 1986. Results for pH are presented in Table 1.3.

00003

Table 1.1

Results of the Metals Analysis

WA# 3476 NATIONAL LEAD IND. SOIL SAMPLES

Concentration reported in mg/kg

Cl	ient #	808794	808795	808796	808797	808798	808799	
Lo	cation:	Lead	Lead	A Pile	B Pile	C Pile	D Pile	
		Oxide A	Oxide 8					
*	Sol i d s	88.0	97.1	99.3	88.4	93.2	74.4	DETECTION
Parameter:								LIMIT
Aluminum		1400	800	94000	8700	11000	12000	50
Antimony		970	2500	12000	1100	400	300	1
Arsenic		400	690	1000	1600	1400	1200	1
Barium		770	40	800	650	1400	1300	2.5
Cadmium		1000	800	300	50	350	260	2.5
Chromium		100	110	160	200	150	130	5
Copper		630	2400	31000	2750	2500	3060	5
Iron		12000	15000	130000	100000	110000	130000	10
Lead		480000	350000	130000	120000	130000	110000	50
Magnes i um		780	860	19000	2000	1500	2040	5
Manganese		300	50	480	640	1100	1100	5
Mercury		2.10	2.60	0.02	0.10	0.02	ND	0.02
Nickel		380	630	640	890	470	800	5
Selenium		ND	ND	1	5	1	2	0.5
Silver		8	11	6	6	4	6	2.5
Zinc		1120	4000	40000	3500	3050	5570	2.5

ND denotes not detected

Table 1.2

Results of the Metals Analysis

of TCLP extracts

WA# 3476 NATIONAL LEAD IND. SOIL SAMPLES

Concentration reported in mg/L

Client #	C8794	c8795	C8796	c8797	c8798	c8799	Method
Location:	Lead	Lead	A Pile	8 Pile	C Pile	D Pile	Detection
	Oxide A	Oxide 8					Limit
Parameter:	_						
Arsenic	ND	0.282	ND	ND	ND	ND	0.10
Barium	ND	0.199	ND	ND	ND	ND	0.10
Cadmium	24.1	26.3	1.4	1.6	5.3	0.69	9.10
Chromium	ND	ND	ND	ND	ND	ND	0.10
Lead	620	2750	8.0	4.9	5.1	4.5	0.10
Mercury	ND	ND	ND	ND	ND	ND	0.10
Selenium	ND	ND	ND	ND	ND	ND	0.10
Silver	ND	ND	ND	ND	ND	ND	0.10

ND denotes not detected

Table 1.3 Results of Hardgrove Grindability Index, Bulk Density pH, and Cation Exchange Capacity

WA # 3476 National Lead Industries

			Cation
			Exchange
			Capacity
Sample ID	Location	рH	(meq/100g)
		=======================================	********
8794	Lead Oxide A	9.7	2.2
8795	Lead Oxide 8	6.8	5.7
8796	Pile A	4.4	12.1
8797	Pile B	7.4	8.3
8797 Dup	Pile B	7.3	8.3
8798	Pile C	7.1	6.5
8799	Pile D	7.6	17.0

Sample ID		Hardgrove Grindability Index	Bulk Density (mg/L)
8794	Lead Oxide A	109	3.31
8795	Lead Oxide B	122	3.02
8796	Pile A	103	2.44
8797	Pile B	108	2.22
8797 Dup	Pile B	109	2.26
8798	Pile C	121	2.35
8799	Pile D	122	2.47
22222222			

00006

Figure 1.1

Lead Oxide A




Figure 1.1

Lead Oxide B




Figure 1.1
Pile A




Figure 1.1

Pile B





Figure 1.1

Pile C


National Lead Industries, WA # 3476



00011

Figure 1.1

Pile D



00012

QA/QCPROCEDURE FOR METALS

EMSL WP 989 #1, WP 186, WP 287, WP 988 ICAP 19, and WP 988 #7 were used to check the accuracy of the calibration curve for the soil analyses. The percent recoveries ranged from 45 to 155 and were within the 95% confidence limits. The results for the EMSL analyses are listed in Table 2.1.

Sample B08797 was chosen for matrix spike/matrix spike duplicate (MS/MSD) analyses for the soil samples. The percent recoveries, listed in Table 2.2, ranged from 6 to 123. The relative percent differences (RPDs), also listed in Table 2.5 ranged from 9 to 96.

The results of the spike blank analysis, associated with the soil samples analyses, are reported in Table 2.3. The percent recoveries ranged from 90 to 114.

Table 2.1

Results of the EMSL for National Lead Ind. Soil Samples

Concentrations reported in ug/L.

METAL	EMSL	#			CONC. RECOVERED	TRUE VALUE	95 % CONFIDENCE INTERVAL	% RECOVERY
Aluminum	WP	287			567	500	423-623	113
Antimony	WP	186			31	20	7.87-31.4	155
Arsenic	WP	989	#1		45	50	38.9-60.3	90
8arium .	WP	989	#1		111	100	77.1-133.9	111
Cadmium	WP	287			26	25	21.2-27.7	104
Chromium	WP	287			111	100	84.4-115	111
Copper	WP	287			107	100.0	89.4-109	107
Iron	WP	988	ICAP	19	985	1000	N/A	99
Lead	WP	988	ICAP	19	958	1000	N/A	96
Magnesium	WP	988	ICAP	19	967	1000	N/A	97
Manganese	WP	287			99	100	88.4-109	99
Mercury	WP	989	#1		2.0	4.4	1.46-2.58	45
Nickel	WP	287			101	100	84.1-116	101
Selenium	WP	989	#1		53	50	36.1-55.5	106
Silver	WP	988	#7		1048	1000	N/A	105
Zinc	WP	287			105	100	85.9-115	105

N/A - Not available

Table 2.2

Results of Matrix spike/Matrix spike duplicate Analysis

WA# 3476 NATIONAL LEAD IND. SOIL SAMPLES

Concentration reported in ug/kg

Sample # 808797

METAL	SAMPLE	ORIGINAL CONC.		RECOVER	RED CONC.	% REC	OVERY	RPD
	CONC.	Spike	Dup.	Spike	Dup.	Spike	Dup.	
Antimony	1118812	4950	4902	**	**		-	
Arsenic	1619802	4950	4902	**	**	-	-	•
Barium	644950	9901	9804	**	**	-	-	•
Cadmium	47426	99010	98039	157327	145196	111	100	11
Chromium	217327	99010	98039	295347	305392	79	90	13
Copper	2751782	99010	98039	**	**	-	-	
Lead	118514851	99010	98039	**	**	-	•	-
Manganese	637723	99010	98039	749604	738333	113	103	10
Mercury	97	1109	1077	1264	1422	105	123	16
Nickel	890000	99010	98039	**	**	•	•	-
Selenium	4653	4950	4902	4950	5490	6	17	96*
Silver	5545	99010	98039	69604	75196	65	71	9
Zinc	3472772	99010	98039	**	**	-	-	-

No spike required for aluminum, magnesium, and iron.

^{**} - Not recovered or poor recovery due to higher concentration of analyte in sample

^{* -} poor recoveries due to matrix interference

Table 2.3

Results of Spike Blank Analysis

WA# 3476 NATIONAL LEAD IND. SOIL SAMPLES

Concentration reported in ug/kg

METAL	Spike Blank	Concetration Recovered	% Spike Recovery	
Aluminum	84746	96610	114	
Antimony	4237	4153	98	
Arsenic	4237	4068	96	
Barium	8475	8898	105	
Cadmium	84746	81610	96	
Chromium	84746	89915	106	
Copper	84746	84576	100	
1 ron	84746	80763	95	
ead	84746	81356	96	
lagnes i um	84746	87288	103	
Manganese	84746	83051	98	
Mercury	990	1030	104	
Nickel	84746	84746	100	
Selenium	4237	4661	110	
Silver	84746	87373	103	
linc	84746	76102	90	

QA/QC FOR TCLP METALS

Sample C8796 was chosen for the matrix spike analysis of the TCLP extracts. The recoveries are listed in Table 2.4. They range from 89 to 101. The recovery separately reported for lead (57 %) was from a different project sample analyzed along with the NL Industries sample batch by the laboratory.

Table 2.4 MATRIX SPIKE

Project #3476 National Lead Industries

Sample ID: C8796 (NL Ind.)*

	=========	========		
	Spike	Sample	MS	
Parameter	Added	Conc.	Recov.	*
	(mg/L)	(mg/L)	(mg/L)	Recovery
=======================================		========	*******	
Arsenic	1.00	ND	1.00	100
Barium	1.00	ND	0.98	98
Cadmium	1.00	5.30	6.00	70
Chromium	1.00	ND	0.97	97
Mercury	1.00	ND	0.97	97
Selenium	1.00	ND	1.01	101
Silver	1.00	ND	0.92	92
		=======	=======	

ND denotes Not Detected

Table 2.4 MATRIX SPIKE

Project #3476 National Lead Industries Sample ID: *

*******************	******	=======	22222222	=========
	Spike	Sample	MS	
Parameter	Added	Conc.	Recov.	x
	(mg/L)	(mg/L)	(mg/L)	Recovery
	=======		*******	222222222
Lead	1.00	7.70	8.27	57
		=======		

ND denotes Not Detected

^{*} The MS analysis for lead was performed on a sample from another site, and is reported below.

^{*} The MS analysis for lead was performed on a sample from another site.

CHAIN OF CUSTODY RECO /LAB WORK REQUEST No: 3293 REAC, Edison, N.J. Natural Industries Project Name: SHEET NO US **EPA Contract 68-03-3482** Project Number: RFW Contact: Taloia Phone: 632-4300 Due Date SAMPLE IDENTFICATION **ANALYSES REQUESTED** Sample No. Sampling Location Matrix Date Collected Container/Preservative B8794 16 02/Num Lead uxide . A 2/19/91 B8795 Lend Oxide B B8796 APIL 402 Nive B 8797 BP:le 8 8748 C Pile 11 B 8799 D P.L Return all Note: unusal sample in orginal Rich Tobia Special instructions: * As, Bu, Cd, Cr, Ph, Hy, Se, Ay, Zn, AI, Fe, Mg Drum Solide Ci, Ni, Mn, Sb DL. Drum Liquids X- Other Rollnguiched By Received By Time Items/Resson Relinquished By Received By 215/1 37. 30

Date

Time

Roy F. V

ion. Inc.

Roy F. Weston, Inc.
REAC, Edison, N.J.
EPA Contract 68-03-3482

CHAIN OF CUSTODY RECORD/LAB WORK REQUEST

National Las Judus tres Project Name: 334-7 -21 -01 -34-76 Project Number: Phone: 631-4200 Due Date: RFW Contact:

3295	,	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
SHEET NO.	!	18.

9102200

SAMPLE IDENTEICATION

ANALYSES DECHESTED

7/02273	SAMPLE IDEN	SAMPLE IDENTFICATION			ANALYSES REQUESTED					
Sample No.	Sempling Location	Metrix	Date Collected	Container/Preservative	Hack need	Exchenge	G-raizize	Bulk	PH K	
A 8794	Lend Oxida A	ک	2/14/91	32 02 None		X		×	K	
D 8794	Land Gride A			#/602/N.~e	×					
A 8795	Lead axide B			32 02/Nune		~	K	X	X	
D 8795	Loud Oxide B			16 og pine	\times					
A 8796	APIL			32 02		_ >_	×	7	7	
D 8796	APile			802	X					
A 8797	BPile			3202		K	بح	بعر	حع	
D 8797	BPILE			802	X					
A 8798				32 0=	<u> </u>	×	×	10	ع	
D 8798				802	K	<u> </u>				
A 8799	D Pile	W		3202	 	<u> </u>	<u>×</u>	عع	٧	
D 8799	DPile	V	V	8 05	×					
		<u> </u>			<u> </u>					
		ļ				<u> </u>		L		
					<u> </u>			l		
		<u> </u>								
						<u> </u>				
		 				<u> </u>		<u> </u>		
		ļ			<u> </u>					
								1		

Metrix:

Special Instructions: D sample 18-35 nesh

Soff DS- Drum Solids DL. Drum Liquids W. Water O- OI X- Other

Relinquished By	Received By	Pate	Time	Items/Resson	` Relinquished By	Received By	Date	Time
Pruli Atri	Schulter	2 20 91	9 2			B. Hedon	2-22-91	4/30
J	0							1
		1	1					
		†	, –				-· \	·
	- 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1							

NLD	
001	
0185	

Roy F.	ston, Inc. C	HAIN	OF CUST	ODY RECU	LAB WO	ORK REQUEST	No: 3294		
REAC, Ediso EPA Contrac		ject Name: ject Numbi V Contact:	Nat 334	1 -21 -01 - Phone	Indus 34.76 632-4200	Due Date	SHELLIN	1	. 1
	SAMPLE IDEN					ANALYSES R		1) 10	
Sample No.	Sampling Location	Matrix	Date Collected	Container/Preservative	<u> </u>	*		I	
C 8744	Lend Uxida A	S	2/19/41	1602/Nine					
C8795	Pile A	+{-			X		FEB 27 15	991	i
C-2746								İ	1
6-8946							-		
C8797	PileB	 	 					1	
(8798	PileC		1.//	· · · · · · · · · · · · · · · · · ·	×	· · · · · · · · · · · · · · · · · · ·			
C 8799	P:12D	V	V		×			:	
								İ	
					 				}
		 							
			 		- +				
			<u> </u>	 					
	-	 							
,							-		
								1	
Matrix:		etructions:	* TCL	-P for not	als onl	4			
S- Soil DS W- Water DL O- Oil X-	- Drum Liquids		/	As, Bu, C	d, Cr.	*Pb, Ha,	Se, Ag		
Items/Resson	Belinquished By	, Rej	selved By		ems/Reason	Relinquished By	Received By	Date	Time
6/Andys	is Shiltre	3ch	lunell.	2/26/9, 13-jn					
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\									-
T .							· - · · · ·		† 1



REAC PROJECT GSA RARITAN DEPOT 2890 WOODBRIDGE AVENUE BLDG. 209 ANNEX EDISON, NJ 08837-3679



Galbraith Labs

February 19, 1991

PO Box 51610

Knoxville, TN 37950-1610

Attn: Bill Longmire

RE:

Project #3347-21-01-3476

NL Industries

Per your phone quotation of February 13, 1991, please analyze the enclosed samples for the following parameters:

# Samples	Matrix	Analysis/Method
6	Soil	TCLP Metals: As, Ba, Cd, Cr, Pb, Hg, Se, Ag

Please run a set of MS/MSD samples on our sample matrix. Note: as per the enclosed letter, two other samples are being sent to you in this cooler for a separate job. These other samples also require a set of MS/MSD samples to be run on one of the two samples.

A complete extended data package is due at REAC twenty-one working days after receipt of the samples by your laboratory, or on Thursday, March 21, 1991. Please read the attached Weston / REAC / ERT Deliverables Requirements for our exact data package requirements. The Roy F. Weston Bonus/Penalty Clauses have also been attached for your reference.

Preliminary results are expected by FAX as the analyses completed. We will be contacting you on a weekly basis for information regarding the analyses.

The cost for these analyses shall not exceed \$1632.00 and may be billed against Purchase Order No. 08-70661. Billing is to be directed to Accounts Payable, Barbara Lawrence.

In case of any changes or problems, please contact me at (201) 632-6923.

Thank you.

Chris Schultze

Chris Schultze

Roy F. Weston, Inc. / REAC Project



REAC PROJECT GSA RARITAN DEPOT 2890 WOODBRIDGE AVENUE BLDG 209 ANNEX EDISON, NJ 08837-3679

ATEC Associates
5150 East 65th Street
Indianapolis, IN 46220

February 21, 1990

FAX 317-849-4278

ATTN: Keith Kline

RE:

Project #3347-21-01-3476

NL Industries

Dear Keith:

We would like to have the enclosed samples analyzed at your laboratory. Please note that a second set of samples has been

enclosed for Grain Size analysis only.

# Samples	Matrix	Analysis	Method	Price
6	soil	Cation Exchange Capacity	SW 846 9080	75.00
6	soil	рĦ	SW 846 9010	
6	soil	Bulk Density	ASTM C854/E12	30.00
6	soil	Grain Size/Hydrometer	ASTM D422	85.00

We require a blank, as well as one duplicate to be run on one of our samples.

Please sign the enclosed Chain of Custody and return a copy of the signed front page to my attention with the complete data package no later than 21 working days past the date of sample receipt, or March 25, 1991

The Weston / REAC / ERT Deliverables Requirements have been attached for your reference along with the Roy F. Weston Bonus/Penalty Clauses. The cost for these analyses shall not exceed \$1770.00, and may be billed against Purchase Order No. 08-70671. Should any questions or problems arise concerning this project; please call me at (201) 632-6923. Thank you.

Sincerely,

Chris Schultze

Roy F. Weston, Inc. / REAC Project

reis Schultze



April 2, 1991

Solid & Hazardous Waste Site Assessments
Remedial Design & Construction
Underground Tank Management
Asbestos Surveys & Analysis
Hydrogeologic Investigations & Monitoring
Analytical Testing / Chemistry
Industrial Hygiene / Hazard Communication
Environmental Audits & Permitting
Exploratory Drilling & Monitoring Wells

Mr. Chris Schultze Weston REAC 2890 Woodbridge Ave. Bld. 209 Annex Edison, NJ 08832-3679

The enclosed paper is as per the request of Mr. John Hunter. Thank you.

Mr. Richard Gehlbach

000%4



REAC PROJECT
GSA RARITAN DEPOT
2890 WOODBRIDGE AVENUE
BLDG 209 ANNEX
EDISON, NJ 08837-3679

May 9, 1991

Gail R. Hutchens
Executive Vice-President
Galbraith Laboratories
P.O. Box 51610
Knoxville, TN 37950-1610

Post-It* brand fax transmittal n	From YQ410 (2-7
To Tail Hutchens	Co. Roy F 10/0 Lan / RE-
Co. (nulbranth Lab	Phone 1908 1 25 - 9015
Fax 9(015) 546 - 720)	Fax 9 (20%)

Dear Mr. Hutchens:

In order to complete our review for Edgewood and National Lead reanalysis data (Galbraith sample number Q-4807 to Q-4814), we need the following questions to be clarified:

- 1) Is sample Q-4814 B the duplicate of sample Q-4814? If not, is duplicate analysis performed?
- 2) Please provide the added amount for all analytes in matrix spike recovery analyses.
- 3) As noted in the raw data, the reading for cadmium matrix spike recovery analysis (4811 spike) exceeded the calibration range. However, no reanalysis data were found in the package.
- 4) Please explain what "peak offset" means.

It would be greatly appreciated if you could respond as soon as possible.

Sincerely,

Yi-hua Lin, Ph.D. QA/QC Coordinator

GALBRAITH

Laboratories, Inc.

QUANTITATIVE MICROANALYSES

ORGANIC - INORGANIC

PHONE 615/546-1335 FAX 615/546-7200

MARRY W JALBRA TH, D. O. CHRISTON OF ITS BOARD A ENGLISH REQUEST TO WELLOW RECORDANT TRANSPORT OF THE STRONG T

FAY TRANSMITTAL COVER SHEET *****

DATE	May	14, 1991		
TO	Dr.	Yi-hua Lin		
	Roy	7. Weston		
PAZ	# (90	6) 632-9205		
nesa:	AGE: _	Response to fax		
	-			_
	-			
	-			
	-			
TEAM	K Y00,			
galbe (Paz	vaite la 0 (615	BORATORIES, INC.) 546-7209)		
TOTAL	HUNDER	OF PAGES INCLUDING COVER LETTER:	6	

-STIER AND DISPUDITS BY U.S. MAL - P.S. SEZ SEED, MACKYELLE TH 37850-1610, OTHER CLARGES - 2523 SYCAMORE OR, MACKYELLE TH 37857-750
ESTABLISHED 1000

THE MAN MAN - 1 AM

QUANTITATIVE MICROANALYSES ORGANIC — INORGANIC PHONE 618/846-1206 PAX 618/546-7208 METWORK METOWARE

ONG TRING

May 13, 1991

00027

2890 Woodbridge Avenue Building 209 Annex Edison, New Jersey 08837-3679

Dear Dr. Lin:

Your correspondence outlining questions on the analysis of Galbraith sample numbers Q-4807 to Q-4814 (Edgewood and Retional Lead reanalysis data) has been forwarded to me for action.

- A response to each item of concern follows:
- 1, Q-4814 B is the duplicate of sample Q-4814.
- 2. Each analyte in matrix spike recovery analyses was added as a 100 microliter aliquot of a stock 1000 microgram/milliliter solution into the 100 ml of leachate.
- The report of the over-range cadmium spike reading was an oversight. The reanalysis is proceeding and will be sent with accompanying raw data when available.
- 4. "Peak offset" is a term generated by Perkin-Elmer software whenever no measureable emission peak is present.

During our review of the rew data, we found that the data sheets containing the original weights of sample taken for the leachates had been inadvertently emitted from the rew data mailing. Copies are enclosed. These data are not entered into our database and consequently have no summary sheet.

We apologize for the oversight and hope that no irremedial damage was done. If I can be of any further assistance please do not hesitate to call.

Sincerely,

Robert L. Logan

Robert L. Logan Director of Quality Assurance

(1000 mg/ml) x . Xml/. XL

1,000 ug/L

12000 mg/L

Extended Page 1942

SALERATIN LABORATORIES. ING.

PROCEDURE: EP TEX MALE Open Form I INSTRUMENTAL METHODS PROCEDURE 1:13/2" 64 EXACT COPY OF RAW DATA Belance: /75:-3 FOR RESULTS REPORTED INSTRUMENT: 51/ " Analyst: 187 DATE: 1/1/91 -Mail Otal OA MAY 1 0 mah psf Semple # 4821 ratu £ 4131 48CE 7384 Est ion te BJ 1.7 Sample State Cross Wt (Tare Wt () 113.30 K4.56 130.78 Sample Wil of -18107a tca:ca 10.1-1-1-1 Colibration 5.95B B.45 6.941 7.30 1.24 on extraction Unit 4.012 6.997 2000 2000 2000 A Machon there 4.91 288 4.40 5 use 3.5 million 50° 8.64 16 m. a. Product pha 17 5.11 1.88 4.53 K. 5 & Abrack or Smell to 5 extent con Healt 18 h boch one 2:50 Wills Results Const 7.441 4.901 5.313 Ext. flend 5 = 5144 Word, 44 and Actio face and the

)

)

)

001 0195

NLD

Open Porns 1 INSTRUMENTAL METHODS Bolance: / 720 3	PROCEDURE #	DE EX	FOR RESUL	OF RAW DATA
Analyst: 26 8	INSTRUMENT: DATE: 4/	131 1117 - 4-129	4-	4/17-11
Septe 1 D HEID	480	4912	4813	4814
Estimate A	Æ		A	B
Sample State			14	
			0//	
Gress Wt ()			//	
Tore W () 135, 395			1169	117-4
Sample Wit 1 10 10 100	170.50	138.679	131.0	46.0
V. 1 4				
Californian 7.90	Cestale	Acc	7.29	7.32
nt estantion that 2000	3000	2000		
h extention fluid 3. 90	16.93	4.48	89	4.95
Show i soilable 1				
Loca 10 own		-		
Pleadout Ohic ET F.CI	3. 4	4.65	5.147	1. 9.3
5 (Strade of Head	<u> </u>	I.		IE.
PSARha becellante It			F	
Block we			4/16/71 3:30pm	
are:			4/18/91 B.D. R. 34 Am	
Result of Mark 5 227				
know 15 2.27	5.135	5.978	5.81	5.882
· · · · · · · · · · · · · · · · · · ·	<u> </u>	/		124
Commanity:	,	ypos	Colculations:	J.

)

NLD

	Open Form 1 INSTRUMENTAL METHODS Balance: \ 10 \ 3	PROCEDURE: EPTOY XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	EXACT COPY OF RAW DATA FOR RESULTS REPORTED APR. 19 1001
Amilysti 288		DATE: 417-91	QA NOTY 1 O MOS
	Sample (34:36		
1	Estimate ConTable		
	Smple State		
	Gross M ()		
Ì	Tare Wi ()		
	Sample W1 4/1 75,20		
	California 1.145		
-	mb estruction 4 1 1500		
,	shawing a send 4. 98		
1	>5 um 1.5 midel		
	1000 D		
	Rendout JAGIA 2.68		
	A Sixthe tuning To		
	2 Sex bakenkele		
	Ele 2 de ar 6 3:30 9/16/21		
	Results of Fry		
	Results Of St. F.		
	Kerrel 14- 16/18		
	Of the mediate ()		
	Commonts:	Cel	culations
	1	1	

GALBRAITH

Laboratories, Inc.

QUANTITATIVE MICROANALYSES

ORGANIC - INORGANIC

PHONE 615/546-1335 FAX 615/546-7209

HARRY W GALBRAITH PAD CHAIRMAN OF THE BOARD KENNETH S WOODS PRESIDENT VELMA M RUSSELL

VELMA M RUSSELL SECRETARY-TREASURER DAVID J STROM

SENIOR VICE PRESIDENT

GAIL R HUTCHENS

EXECUTIVE VICE PRESIDENT

WILLIAM M LONGMIRE VICE PRESIDENT TECHNICAL SERVICES

May 21, 1991

Ms. Chris Schultze Weston REAC Project 2890 WoodBridge Road Building 209 Annex Edison, New Jersey 08837-3679

Dear Ms. Schultze:

The following is in response to your questions posed by Dr. Yihua Lin pertaining to our sample numbers Q-4807 through Q-4814. Please forward to her at your discretion.

- 1. The Barium result for Q-4814 is a typographical error.
- The spike matrix for samples Q-4813 (Pb) and Q-4811 (Cd) were miscalculated. Enclosed find the corrected copies of the raw data and a corrected copy of the QC summary.
- 3. The cadmium result for sample Q-4811 (sample and matrix spike) has been repeated and the raw data is enclosed.

We apologize for any inconvenience these errors may have caused.

If we can be of any other assistance, please do not hestitate tp call.

Sincerely,

Ann M. Lescher

Quality Assurance Inspector



00033

DATA VALIDATION

For soil samples analyzed by REAC all QA/QC criteria were met. EMSL calibration curve verification was successfully completed, percent recoveries and relative percent differences for the Matrix spike/Matrix spike Duplicate analysis were all acceptable except for selenium which had low recoveries due to matrix interference. Percent recoveries and relative percent differences for the Blank spike analysis were all acceptable.

TCLP extraction and analysis of extracts was initially completed by the subcontracting laboratory employing single point calibration and the method of standard additions to analyze the extracts. This was deemed unsatisfactory and the extracts were reanalyzed using three point calibration and Inductively Coupled Plasma Emission Spectroscopy, as required by the cited method.

Hardgrove Grindability Index, cation exchange capacity, grain size analysis, pH, and bulk density analysis were all found to be acceptable.